



Albert Einstein Institute
Max Planck Institute for Gravitational Physics and
Leibniz Universität Hannover




lisa pathfinder

LISA Pathfinder

Optical Metrology at L1

M Hewitson
for the LPF Team
LISA Symposium, Zurich
September 2016






- OMS Introduction
- Commissioning
- Performance
- Noise budget
- Structural stability
- Long-term performance

The Optical Metrology System on LPF

Assess relative acceleration of test masses
by measuring their relative motion using an interferometer




Goal is to measure changes with a precision of
a few $\text{pm}/\sqrt{\text{Hz}}$ at millihertz frequencies


The Optical Metrology System




lisa pathfinder




Reference Laser Unit




Laser Modulator



Optical Bench Interferometer



Phasemeter



Data Management Unit


Reference Laser Unit (RLU)



Nd:YAG laser


λ : 1064 nm

Power: 45 mW



Operated at 38mW output power

Modulation



Optical Path Length Difference Correction

$f_1 = 80000500 \text{ Hz}$


$f_2 = 79999500 \text{ Hz}$

$$f_1 - f_2 = 1 \text{ kHz}$$


On the optical bench...



← power stabilisation




Phase measurement






for each of the 4 interferometers...



to DFACS...




Data Management Unit

control feedback signals

modulation unit
& laser...


The 4 Interferometers of the OMS



X1 Interferometer

Measures position and orientation of TM1 w.r.t. OB (SC)


The 4 Interferometers of the OMS



X12 Interferometer

Measures position and orientation of TM2 w.r.t. TM1

The 4 Interferometers of the OMS




Reference Interferometer

Measures phase fluctuations common to both optical fibres.

Subtracted from all other IFOs in the DMU.

See poster by Michael Born

The 4 Interferometers of the OMS




Frequency Interferometer

Measures fluctuations of laser frequency.

Used to stabilise laser frequency.

See talk by
Sarah Paczkowski




Commissioning - first light



It was a cold, dark night in early January...


- DMU calibration coeffs updated in DMU
- RLU + **L**aser **A**ssembly redundant chain checkout
 - LA Electronics, B-side, activated
 - DMU to operational mode, OMS processing on
 - Pump diode bench B activated
 - 40 mW RLU output
 - Light detected on some quadrants
- RLU + LA prime chain
 - LA Electronics, A-side, activated
 - Pump diode bench A activated
 - 40 mW RLU output
 - Light detected on some quadrants






1. Switch on and checkout of all units
2. Actuator scans
3. Single beam measurements
(spot positions)
4. Stabilisation Loops checkout
5. RLU performance and operating point
6. Initial performance with low contrasts

Projected Optical Powers on the bench




See poster by Dave Robertson






1. TM optical alignment after release
2. Polarity and gain tests
3. Trimming of powers on the bench
4. Performance with aligned test masses

Alignment of the optical system




- Account for offsets between the inertial sensor and optical reference frames
 - mechanical tolerances build up during the integration procedure
- Switched to optical angular control for TM1 on Feb 18th
- Switched to TM2 optical angular control on Feb 18th

Contrasts before and after alignment



X12: Initial performance with aligned TMs






Source	Coupling	Contribution
Frequency Noise	via arm-length mismatch between measurement and reference beam	$\sim 300 \text{ um mismatch} \Rightarrow 20 \text{ fm}/\sqrt{\text{Hz}} @ 1 \text{ Hz}$
Phasemeter Noise	Quantisation, front-end electronics, etc	$\sim 650 \text{ nrad}/\sqrt{\text{Hz}}$ per channel $\Rightarrow 28 \text{ fm}/\sqrt{\text{Hz}}$
RIN	Couples at $2x f_{\text{het}}$	~ 0 for correct operating point
RIN @ DC	Not relevant for OMS performance, but creates fluctuating forces on TMs	$\sim 2 \text{ fm s}^{-2} / \sqrt{\text{Hz}} @ 0.1 \text{ mHz}$

+ other, less significant sources

Relative Intensity Noise coupling



- Need to consider RIN @ dc, 1f, 2f...
 - 1f cancels due to balanced detection
 - 2f does not, and depends on absolute phase difference between two beams
 - RIN @ dc contributes to force noise budget

See talk by
Andreas Wittchen



RIN @ dc - photon pressure



- RIN @ dc imparts a force on the TMs via momentum transfer from reflected and absorbed photons
- Fluctuations in the laser intensity result in a fluctuating force

$$\Delta g_{dc}^{RIN} = 2 \times \frac{2.6 \text{ mW} + 1.25 \text{ mW}}{M_{TM} \times c} \approx 13 \text{ pm s}^{-2}$$

$$S_{\Delta g}^{RIN} = 2 \frac{S_P}{Mc}$$



Preliminary

See poster by
Natalia Korsakova


- coupling of TM/SC jitter to differential readout via:

- TM alignment
- beam properties
- PD construction (slits)
- ...

- minimise by:


- subtracting on ground
 - ad-hoc fit, or physical model
- alignment of TMs

See poster by
Gudrun Wanner




$$\Delta x \approx \Delta \phi \Delta y$$

Cross-talk in Δg - software subtraction




Cross-talk in raw Δg - TM alignment



Noise budget




Segment: (start: 2016-03-21 02:00:00.090 UTC end: 2016-03-26 07:59:45.090 UTC)




DWS Noise Budget




Segment: (start: 2016-03-13 16:30:00.087 UTC end: 2016-03-15 07:00:00.087 UTC)




Stability of OMS performance



Long-term monitoring



See poster by Heather Audley



- The OMS is a complex system with many 'moving' parts
- The system needs routine/daily monitoring to ensure good 'health' and high performance
- AEI + APC + ASD + UGL + IEEC provided daily reports on each subsystem
 - powers, voltages, currents, stability, performance...



- The optical metrology system on-board LPF is a **resounding success**
- Performance about **x100 better** than achieved on ground
- **High-stability** and reliability
- Very little maintenance required
- **High-performance** allowed us to explore **cross-talk** at unexpected levels
- Concepts and design techniques are **proven** and ready for use in LISA

Thanks to all LPF Team



Supported by:



Federal Ministry
for Economic Affairs
and Energy


on the basis of a decision
by the German Bundestag

additional material

RIN @ the laser



RLU Reletave Intensity Noise



Noise budget from theoretical considerations

