

foto:
MAURIZIO PERCIBALLI

Status of the Virgo

INTEGRATION
WEST END metal
26 luglio 2016


Fulvio Ricci

on behalf of the Virgo Collaboration



- Advanced Virgo Integration
- AdV Commissioning
- Preparing O2 for new discoveries: EM follow up & Computing effort
- A vision of the AdVirgo future
- Conclusions

Advanced Virgo Integration

AdV in summary




Larger central vacuum links




Large cryotrap

new IP tilt control



Four Cryotrap
in operation





Absorption < 0.5 ppm

Flatness ϕ 150 cm < 0.5 nm

Test mass I ROC 1424 m

Test Mass E ROC 1690 m

Test Mass 42 kg

Diameter 350 mm

Thickness 200 mm

Beam Splitter 50%


Weight 43 kg

Diameter 500 mm


Thickness 100 mm

BS flatness ϕ 220 cm \leq 1 nm




New baffles have been produced and installed



Thermo Compensation System





- Actuators completely installed (CO₂ lasers, ring heaters)
- HWS benches assembled, final integration almost completed.




Fine alignment of visible aiming beam on CPs completed






Detection System

- ❑ 6 benches placed in vacuum chamber
- ❑ 2 (SDB1 and SNEB) suspended and controlled
- ❑ SNEB in vacuum





14 DAQ Boxes in benches
 25 DAQ Boxes in racks
 25 ADC7674 boards in racks
 12 new real time PCs

WEB
 3 ADC7674 boards
 3 DAQ Boxes

TCS
 5 ADC7674 boards
 1 DAQ Boxes

NEB
 3 ADC7674 boards
 3 DAQ Boxes


Control B.
 16 RT PCs

Mode Cleaner B.
 2 ADC7674 boards
 1 DAQ Boxe

Injection
 6 ADC7674 boards
 8 DAQ Boxes



Detection
 3 ADC7674 boards
 5 DAQ Boxes

CEB Environment
 3 ADC7674 boards






*Suspensions of the mirror test masses:
Super attenuator +
Payload*

*Optical Benches:
Short length
Super attenuators*






- 13 broken blades of the seismic filters of the mirror suspensions
- 1 broken blade of the seismic filters (G.A.S.) to suspend optical benches
- Cause identified: *Hydrogen embrittlement of the Maraging steel.*
- Substitution of the broken and suspected blades: 161/260
- 120 extra blades built and characterized



10 μ m EHT = 20.00 kV Signal A = SE1 Sample ID = Virgo blade 340 fracture surface
WD = 12.0 mm Mag = 2.87 K X Photo No. = 4

- With the mirrors suspended under vacuum, we experienced failures of the monolithic suspensions
- In order to do not stop the commissioning we implemented a steel wire suspension to replace the broken ones.
- At present all mirrors suspended in vacuum and the commissioning activity is progressing
- *Investigation on the failure cause continue (Micro bubbles in the suspension? Material default?)*




All the main parts of hardware are on-site and are installed

Final NI payload installation TBD soon

Failure of a NIKHEF blade solved promptly


Commissioning of the North arm done. Arm locked. Light circulating also on CITF

West Input down again: action lan TBD



VIRGO New target based on the present config.

- We feel strongly that it must be maintained the prime goal of participating meaningfully in O_2 and this is still possible with mirror suspensions of steel wires



Steel 300 μm $\phi=10^{-4}$ ($\phi=10^{-3}$)	
BNS Horizon [Mpc]	60 (45)
BBH Horizon [Mpc]	313 (202)

SubSystems	Status
INJ	
MIR	
PSL	Laser for phase 2 not available
SAT	
SBE	
INF	
SLC	
VAC	
PAY	2+1 payloads of the test masses with metallic wires + 1 monolithic
DAQ	
DET	
TCS	Almost Completed--- completed the sensing system
ISC	Hardware for phase 2 under study
OSD C	

June 10, 2016
LAST TOWER
CLOSED



Virgo central hall APRIL 2016



NORTH ARM ready for
commisioning on May:
large vacuum valves opende and
laser light at 3 km!

3000N CC --- mBar
Turbo speed **600** Hz

TCM_3000N_Valve

2400N CC **5.328e-08** mBar
Turbo speed **600** Hz

TCM_2400N_Valve

1800N CC **8.56e-09** mBar
Turbo speed --- Hz

TCM_1800N_Valve

1200N CC **6.237e-09** mBar
Turbo speed **600** Hz

TCM_1200N_Valve

600N CC **3.585e-09** mBar
Turbo speed **600** Hz

TCM_600N_Valve



$\sim 2e-7$
mbar

$\sim 2e-8$ mbar
(it was $\sim 5e-9$ before the
valve opening)

$\sim 4e-7$
mbar



AdV Budget





- Total cost 21.1 M€ (+2 M€ of Nikhef nominal contribution)
- Comm. Budget ~ 92%
- Contingency residual ~10%

AdV Commissioning

First milestone: the lock of PR-NI Cavity

- A good integrated test for the
- upgraded super attenuators,
 - new payload design,
 - new control electronics,
 - - digital demodulation,
 - - new acquisition/locking software,
 - - use of ring heater of the TCS system

Achieved on March, after the decision to suspend the NI mirror with steel wires







Second milestone: the lock of North Arm Cavity

- Light sent at the end of the North arm on May 4 and the beam found shortly afterwards at 3 km of distance

- High finesse cavity locked on May 22
 - Preliminary optical characterization shows that parameters are as expected

After a recent optimization lock duration record: well over 1.5 day!





- Signals now available on most of the photodiodes
- The two short output mode cleaners are in operation


End Benches Suspended and Vacuum Test started

Crucial test of the system with the photodiodes and the related electronic under vacuum

Test started on August 18 on the Suspended North End external Bench (SNEB)








2 photodiodes on under vacuum → Power increase 10 W (up to a total of 120 W)

Thermal transient few hours



Third milestone: the lock of West Arm Cavity


- Light sent at the end of the North arm on July 28 and the beam found shortly at 3 km of distance
- High finesse cavity locked on August 17
 - Preliminary optical characterization on the way



Fourth milestone: the lock of the full Interferometer

Strategy based on the use of the
variable finesse method

To be done soon!!



*First lock the DOFs with the
Michelson at half of the fringe*

*Then slowly flip on the dark
fringe curing the thermal
aberrations*

Achieve stable 1st lock

Address issues to to MSRC configuration (thermal aberrations). Requires smart use of TCS

Improve the stability and reliability of the lock

Noise hunting and reduction



Optimize the sensitivity curve

Join O2 to detect GW signals




Preparing O2 for new discoveries:
EM follow up & Computing effort

VIRGO Starting point of O2: the O1 detections



Sky Locations of Gravitational-wave Events GW150914, GW151226 and Candidate LVT151012



Sky localizations
90% credible areas of about

620 deg² GW150914

1600 deg² LVT151012


1000 deg² GW151226

Great success of the e.m. follow up program.

20 groups reacted to the circular sent to astronomy community

New groups admitted to the program for O_2

- AGILE, (X-ray and Gamma ray astronomical satellite)
- DWF, (Deep-Wide-Fast program to survey the sky with LSST)
- DLT40, (Frequent survey of galaxies closer than 40 Mpc)
- GROND, (GROND 7-channel imager mounted at the 2.2 m telescope at La Silla-ESO)
- HUNTSMAN, (8 Cannon telephoto lenses used to rapidly scan the GW error box)
- IKI (Gamma-ray burst follow-up capabilities of Russian Space Research Institute -IKI)
- COSI (Compton Spectrometer and Imager , balloon-borne wide-area gamma-ray survey)




Simulated Sky Locations of O1 Events and Candidate Including the Virgo Interferometer

Sky localizations
90% credible areas of about

10-20 deg² GW150914

1000 deg² LVT15012

600 deg² GW151226



Effort to increase the Virgo off-line Computing for O_2

- ✓ Successful effort to harmonize the CNAF software environment with the LIGO one

- ✓ Virgo able to provide already off-line computational power of 25 kHS06_per_year* (via CC-CNAF) → 6% of the total computational power (~420 kHS06_per_year)

- ✓ Effort to increase our contribution
 - Wigner: 2Mhours of CPU, no GRID compliant –difficult to be used,
 - Polgrav: 3Mhours of CPU, GRID compliant , high performance
 - Nikhef: 25kHS06 (as CNAF), GRID compliant, Test to be done

*** 1 kHS06 → 1 Tflop (double-precision peak) →100 CPU cores as of 2012**

- ✓ During the conferences of the summer season, we collected a lot of different predictions and beats for a new discovery. Apparently the winner seems to be:


NS-BH!

Just one citation: Nakamura summary talk @ GWPAW2016 in Boston.

<< *Now as for chirp mass , BBH >> NS-BH >> NS-NS*


- *The detectable range is proportional to 5/6 power of the chirp mass and the volume is 5/2*
- *So that BBH is the easiest detectable source.*
- *Following this tendency in O2, I predict*
- *NS-BH will be observed !! >>*

Upper Limits Rates of BNS and NSBH Mergers from O1



(Abadie *et al.* 2010-Class. Quant. Grav. 27, 173001 ; Kim *et al.* 2015 Mon. Not. Roy. Astron. Soc. 448, 928; Fong *et al.* 2015 , Astrophys. J. 815, 102 ; Siellez *et al.* 2014 , Mon. Not. Roy. Astron. Soc. 437, 649 ; Coward *et al.* 2012 , Mon. Not. Roy. Astron. Soc. 425, 1365 ; Petrillo *et al.* 2013 , Astrophys. J. 767, 140 ; Jin *et al.* 2015 , Astrophys. J. 811, L22 ; Vangioni *et al.* 2016 , Mon. Not. Roy. Astron. Soc. 455, 17 ; de Mink and Belczynski 2015 Astrophys. J. 814, 58 ; Dominik *et al.* 2015 , Astrophys. J. 806, 263).

(Abadie *et al.* 2010 Class. Quant. Grav. 27, 173001 ; Fong *et al.* 2015 , Astrophys. J. 815, 102; Coward *et al.* 2012 Mon. Not. Roy. Astron. Soc. 425, 1365 ; Petrillo *et al.* 2013 , Astrophys. J. 767, 140 ; Jin *et al.* 2015 Astrophys. J. 811, L22 ; Vangioni *et al.* 2016 Mon. Not. Roy. Astron. Soc. 455, 17 ; de Mink and Belczynski 2015 Astrophys. J. 814, 58; Dominik *et al.* 2015, Astrophys. J. 806, 263)



NS-BH Rate

A vision of the AdVirgo future

- Goal for the next decade: maximize the scientific output of AdV
 - Maximize data taking
 - Minimize downtime
- Phase 1 (2017):
short term actions to prepare new implementation between O2 and O3
- Phase 2 (2018-2021):
pushing toward the nominal sensitivity of AdV
- The far future (>2021)
attempts for a further increase of the AdV sensitivity, useful also in view of a new infrastructure

3 step process



Signal Recycling

R&D for Better Mirrors

Squeezing frequency independent

Newtonian Noise cancellation Test

Higher Power Laser

Parametric Instability Control

Squeezing frequency dependent

Implementation of Newtonian Noise cancellation

Reduction of the suspension thermal noise

Magnetic noise reduction

Alignment Control Noise

Heavier Mirrors

Larger Beams

Different beam profile

Suspension change

Better coatings

Long recycling Cavities

Improved TCS

Review of the squeezing strategy


Test of an ALS system based on the fiber technology :

-Output power : 43 W

ALS1 tested for 2400 h, ALS2 tested for 3900 h

-Tested with respect to noise issue and found to be compliant with the AdV specifications

-- Effort on the way to go up to 100 W



Test of the new NeoLAS Solid State Laser:

- NEO Lase (Germany) has designed a 100W based on a 4 stages solid Nd-YVO4 rods Seeded by a 20W
- 100 W module is an upgrade of the 60 W amplifier used now for Adv Virgo
- Contact among NEO Lase, Virgo group in Nice and AEI -Hannover for testing this solution

Whatever the system will choose, we are targeting a coherent combination → 2x100W based on medium power amplifiers


Green Line SHG+MZ+MC532

OPO Line OPO cavity


Homodyne line MC1064+ homodyne

Other OPLL, electronics

- SHG - Second Harmonic Generation
- MZ - Mach Zender for power stabilization
- MC532- Green light mode cleaner
- MC1031- Infrared light mode cleaner
- OPO - Optical Parametric Oscillator
- OPLL – Optical Phase Locked Loop




Green Line		OPO line	
SHG	Installed	OPO	Installed and test started
MZ	Installed	OPLL and electronic	
MC532	Installed		
Homodyne Line		OPLL PCB	Ready
MC1064	Installed	DCC	Ready
Homodyne	Installed	Main Controls	Work in progress



Test on New. Noise cancellation

Modelling NN for Virgo is not simple: we need to understand

- Seismic correlation
- Seismometer placement
- Structural response to seismic sources at various locations
- Nikhef developed a dedicated sensor in the context of a large project supported by Shell.
- The low cost sensors permits to deploy a lot of them to characterize the seismic properties of the location
- Plan is to bring them to the EGO site in the nearest future




In addition INFN Naples built already a tilt meter in the specifications for NN cancellation. We idea is to test a prototype at the Virgo site

Conclusion





The advanced GW detector network: 2015-2025




Source Localization of the Network:

3 , 4 , 5 detectors



Credit: S. Fairhurst




- Virgo is at the end of the integration phase and we are commissioning the interferometer in the new configuration.
- We faced few unexpected crisis and we reacted to preserve our main scientific target: to be online for O2
- We are preparing the near future of AdVirgo:
 - Choice of the new laser
 - Squeezing bench in preparation
- Discussion ongoing on the middle and far term plan




Thank you for the attention

The end....

Extra Slides






SAMPLE 1 - WELDING

3 DOWN

FRACTURE
LINE

BUBBLES





*LIGO Livingston
USA*



*Virgo
Italy*



*LIGO Hanford
USA*





*KAGRA
Japan*



Preliminary Joint LVC Plan for the Second Observation period O2

2016

2017




Different scenarios for the restart after the pause



- Commissioning – Data production **On**
- Engineering Run – Data production **On**
- Downtime – Data production **Off**
- Observing Run – Data production **On**
- Small fraction of time in observing mode
- Detector in observing mode for a fraction of time
- Different scenarios for the restart after the pause
- Detector in observing mode 24/7 – EM alerts

Decision point



AAS conference - June 15th @ San Diego



LSC spokesperson



Virgo spokesperson




LIGO director

The Virgo collaboration congratulate the LISA team on the great success of the Pathfinder mission.

It paves the way for the future LISA mission that we wish to be approved as soon as possible.

Gravitational Wave detectors on the Earth and in the Space will be the main actors of the new era of astronomy and astrophysics.



Thank you for the attention!